



October 28, 2025

ADDENDUM I

RFB Title: LC Main Campus Replacement of Sewer Line Project

To participants who are participates of the RFP# 25-1010

Addendum I: Changes in scope of work:

Line 2: Provide and install one 48-inch **fiberglass** manhole.

Line 3: Provide and install 6-**inch**, two way cleanouts.

Line 5: Remove and replace street asphalt **with concrete** no asphalt.

Add line item to scope of work:

Line 7: Remove and replace if any irrigation system wiring or piping.

Line 8: Break and replace 4-inch concrete with mesh on walkway behind the Adkin Building.

Line 9: Break and replace 8-inch concrete with rebar walkway between the Adkin Building and The Event Center. Approx 25 feet wide walkway. (Note: LC will provide pavers)

Requirements:

- Contractor, must contact 811 to locate underground pipes and electrical wires.
- Contractor, must have **Performance Bond** and **Payment Bond** as stated in the RFP.

Thank You,

Miguel A. Rangel
Director of Purchasing