



April 28, 2026

ADDENDUM I

RFB Title: LC South Campus Fence Project

To participants who are participants of the RFP# 26-0408

Addendum I: Changes in scope of work:

Project overview:

- The linear feet approximation will change to around 50 linear feet more; the fence needs to as close as possible to the College of Health Science building north side point.
- The fence will run from west to east 7 feet from the sight walk and from north to south also 3 feet from the walkway in a straight line exempt to go around the college sign hill.
- The spacing of the panel between poles will be 8 feet.
- The fence will need 1 coat of primer (antirust) paint and two coats of black exterior high-quality paint.
- The fence panel height will be 6 feet and poles at 7 feet with 2 feet underground anchored with concrete.

Materials:

- Steel post measurements will be 4 x 4 round squared tubes at a tube of 11 gage.

Add line item to scope of work:

Transformer gates at the north side of Billy Hall Building: *Example on the South side of the campus at the Physical Plant Chiller area.*

- Customize two door gates with a height of 8 feet poles 4 x 4 round squared tube anchored with bolt for concrete and welded anchors to the sides of the cedar block fence.
- Two panel gates doors with 2 x 4 frames and 3-inch metal blinds style panel with reinforcement on the back of the panels. Total length of the two-panel gate with poles should be approx. 20 feet.

- Gates painted same as the rails near the transformer ask Physical Plant for the color code.

Requirements Reminder:

- Contractor must contact 811 to locate underground pipes, irrigation line and electrical wires.
- Contractor must have **Performance Bond** and **Payment Bond** as stated in the RFP.
- Pricing will need to include 10% contingency expense.
- Provide an estimation of completion, (ex. 1 month or 3 months)

Thank You,

Miguel A. Rangel
Director of Purchasing